

	00.00.1	kg/eh	LC	OH	Freq	Ehd.	Bouwkosten 38,75						Carbonfootprint 6,00											
							4		5		6		10		11		12							
							mat/eh	tll mat	mu/eh	tll mu	oa/eh	tll oa	totaal	bouw	onderhoud	mat/eh	tll mat	mu/eh	tll mu	oa/eh	tll oa	totaal	bouw	onderhoud
4B	00.00.1																							
92	92.00.3																							
	92.20																							
	92.20.20-1																							
4B	92.20.20-111	opstal: prefab berging (6-8 m2), excl. fundering				1,00 st																		
4B	92.20.20-111	prefab houten berging (6-8 m2), excl. fundering	824,0			1,00 st	-	-	-	-	2.234,13	2.234,13	2.234,13			-	-	-	-	759,56	759,56	759,56		759,55
4B	92.20.20-112	opstal: betonvloer met vorstrand tbv berging				1,00 m2																		
4B	92.20.20-112	zandaanvull.tbv.vloer.grdsl.	1.600,0			0,20 m3	21,30	4,26	1,00	0,20	-	-	12,01			11,35	2,27	1,00	0,20	-	-	3,47		
4B	92.20.20-112	beton (200kg cement)	2.400,0			0,02 m3	68,45	1,03	4,00	0,06	-	-	3,35			388,51	5,83	4,00	0,06	-	-	6,19		
4B	92.20.20-112	p.e.folie aanbrengen	0,2			1,10 m2	0,12	0,13	0,06	0,07	-	-	2,69			0,42	0,46	0,06	0,07	-	-	0,86		
4B	92.20.20-112	bekisting trad.funderingsbalken	3,2			0,96 m2	3,39	3,25	0,70	0,67	-	-	29,29			3,97	3,81	0,70	0,67	-	-	7,84		
4B	92.20.20-112	betonstaalnetten FeB 500HKN	1,0			4,50 kg	0,90	4,05	0,01	0,05	-	-	5,79			1,78	7,99	0,01	0,05	-	-	8,26		
4B	92.20.20-112	beton C20/25 funderingsbalken	2.400,0			0,12 m3	76,05	9,13	1,25	0,15	10,53	1,26	16,20			388,51	46,62	1,25	0,15	7,64	0,92	48,44		
4B	92.20.20-112	beton C20/25 vloeren	2.400,0			0,15 m3	76,05	11,41	0,75	0,11	10,53	1,58	17,35			388,51	58,28	0,75	0,11	7,64	1,15	60,10		
4B	92.20.20-112	beton C20/25 toeslag kleinschalig werk	800,0			0,27 m3	25,35	6,84	1,50	0,41	-	-	22,54			129,51	34,97	1,50	0,41	-	-	37,40		
4B	92.20.20-112	mobilele kraan 25 ton (beton)	0,2			0,14 uur	-	-	-	-	106,50	14,38	14,38			-	-	-	-	0,74	0,10	0,10		172,65
4B	92.20.20-211	opstal: fietsenstalling (8 fietsen)				1,00 st																		
4B	92.20.20-211	fietsenstalling (8 fietsen)	499,6			1,00 st	-	-	-	-	2.272,40	2.272,40	2.272,40			-	-	-	-	955,01	955,01	955,01		955,01
4B	92.99																							
4C	00.00.1																							